

Madison County Board of Supervisors

302 Thrift Road

P.O. Box 705, Madison, VA 22727

Telephone: (540) 948-7500

### **ADDENDUM NO. 1**

TO: ALL PROSPECTIVE BIDDERS AND OTHER RECIPIENTS OF CONTRACT DRAWINGS  
AND SPECIFICATIONS

DATE: June 5, 2013

RE: ADDENDUM NO. 1

MADISON COUNTY TRANSFER STATION

CONTRACT DOCUMENTS DATED May 28, 2013

**Receipt of this Addendum must also be acknowledged on the proposal form. Failure to do so may subject the bidder to disqualification.**

### **SCOPE OF WORK / CONSTRUCTION SPECIFICATIONS**

1. Revise specification number one to read as follows:

- 1. Saw cut and remove existing sloped retaining wall and footing per the construction plans. Remove the existing guardrail on the remaining*



*section of retaining wall. Extend the 20' section of existing retaining wall vertically 24" with the following reinforcement:*

- *# 5 rebar vertical doweled 6" into the existing wall with epoxy at 12" on center. Rebar dowels shall be 4" from the vehicular access side of the wall.*
- *# 4 rebar horizontal spaced 3" from the top and bottom of the wall and 6" on center. Dowel rebar into existing foundation wall a minimum of 4" and epoxy.*

2. Revise specification number two to read as follows:

*2. Install approximately 65'-0" in length by 13'-0" tall of new 12" thick reinforced retaining wall with a 16" thick reinforced footing as specified on the construction plans. Footing concrete shall be 3000 psi minimum. Retaining wall concrete shall be 3500 psi minimum and 4-6% air entrained.*

3. Revise specification number seven to read as follows:

*7. Install an 18" guardrail on top of all the newly constructed walls. Guardrail shall be a minimum of 42" above adjoining grade and shall match the existing removed guardrail.*





**Official Content**  
**©Madison County, VA Government**