

MADISON COUNTY REQUEST FOR PROPOSALS

Construction and Site Work at the Madison County Transfer Station May 28, 2013

Introduction:

The Madison County Board of Supervisors are soliciting proposals for construction and site work at the Madison County Transfer Station located at 4592 Shelby Road, Madison, Virginia 22727

Scope of Work / Construction Specifications:

The scope of work for this project will be as follows:

1. Saw cut and remove existing sloped retaining wall and footing per the construction plans.
2. Install approximately 65'-0" of new 12" reinforced retaining wall with a 16" thick reinforced footing as specified on the construction plans. Footing concrete shall be 3000 psf minimum. Retaining wall concrete shall be 3500 psf minimum and 4-6 % air entrained.
3. Remove topsoil and dirt fill to a subgrade with a minimum soil bearing capacity of 2000 psf. Coordinate with owner an approved location on site to stockpile removed soil and fill material. Backfill new retaining wall to grade with compacted # 57 crushed stone.
4. Install 16" square upper and lower storm water inlets with 6" ADS drainage lines to the existing storm water retention.
5. Re-pour concrete over existing 12'-0" x 20'-0" concrete apron (an approximate 3"-6" overlay) and install a new 12'-0" x 35'-0" reinforced 8" thick concrete apron per the construction plans. Extend the existing leachate cleanout to new grade and slope all concrete to the new upper storm water inlet. All slab concrete shall be a minimum 3500 psi and 4-6 % air entrained.
6. Overlay existing asphalt at drop off area with a minimum 2" VDOT SM-2A asphalt. Install a minimum of 4" VDOT BM-2 asphalt over a stone base at the new entrance area as shown on the construction plans. All asphalt shall slope towards the new upper storm water inlet and be installed in accordance with VDOT specifications.
7. Install a 42" tall guardrail at the top of the newly constructed retaining wall. The guardrail shall be installed to match the existing guardrail.
8. Repair and patch asphalt at the retaining wall footing demo area and install a 6'-0" x 10'-0" reinforced 8" thick concrete dolly wheel landing pad as shown on the construction plans.
9. Seed and stabilize all disturbed areas with a contractor's mix seed and straw.
10. The successful bidder will be required to commence work within 7 days of award and complete work within 60 days.
11. The construction area is adjacent to the active transfer station and recycling center and it will be the contractor's responsibility to insure no interruption of the facilities operation and provide for the safety of the public and staff.
12. The bidders, contractors and all subcontractors shall be properly licensed in accordance with the Virginia Board of Contractors regulations and provide the County with their contractor's license and a copy of their insurance certificate naming the County as insured.
13. Attached are details of the project. All requirements are to be confirmed by the bidder.



14. Site visits are encouraged. Contact Roger Berry at rberry@madisonco.virginia.gov or 540-718-6995 to arrange a visit.

15. All work shall be performed in accordance with the Virginia Uniform Statewide Building Code and all applicable county, state and federal regulations. A building permit shall be obtained from the Madison County Building Official's Department; all permit fees will be waived by Madison County.

Bids are due June 7, 2013 before 4:00 P.M. by hand or courier at 301 Thrift Road, Madison VA 22727.

Base Bid: _____

Company: _____

Address: _____

Telephone: _____

Email: _____

Contractor License Number: _____

Insurance Certificate Attached: _____

Authorized Company Officer: _____

Acknowledgment of Addendum #1 _____

Signature: _____

Date: _____

